



DEPARTMENT OF REGULATORY AND ECONOMIC RESOURCES (RER)  
BOARD AND CODE ADMINISTRATION DIVISION

## NOTICE OF ACCEPTANCE (NOA)

MIAMI-DADE COUNTY  
PRODUCT CONTROL SECTION

11805 SW 26 Street, Room 208  
T (786) 315-2590 F (786) 315-2599

[www.miamidade.gov/economy](http://www.miamidade.gov/economy)

Sunshine Windows Manufacturing, Inc.

1745 W. 33<sup>rd</sup> Place

Hialeah, FL 33012

### SCOPE:

This NOA is being issued under the applicable rules and regulations governing the use of construction materials. The documentation submitted has been reviewed and accepted by Miami-Dade County RER - Product Control Section to be used in Miami Dade County and other areas where allowed by the Authority Having Jurisdiction (AHJ).

This NOA shall not be valid after the expiration date stated below. The Miami-Dade County Product Control Section (In Miami Dade County) and/or the AHJ (in areas other than Miami Dade County) reserve the right to have this product or material tested for quality assurance purposes. If this product or material fails to perform in the accepted manner, the manufacturer will incur the expense of such testing and the AHJ may immediately revoke, modify, or suspend the use of such product or material within their jurisdiction. RER reserves the right to revoke this acceptance, if it is determined by Miami-Dade County Product Control Section that this product or material fails to meet the requirements of the applicable building code.

This product is approved as described herein, and has been designed to comply with the Florida Building Code, including the High Velocity Hurricane Zone.

### DESCRIPTION: Series "4302" Aluminum Fixed Window - L.M.I.

**APPROVAL DOCUMENT:** Drawing No. PW01-14, titled "Series 4302 Aluminum Fixed Window - Impact Resistant Glass", sheets 1 through 8 of 8, dated 07/21/14, prepared by manufacturer, signed and sealed by Francisco Hernandez, P.E., bearing the Miami-Dade County Product Control Revision stamp with the Notice of Acceptance number and expiration date by the Miami-Dade County Product Control Section.

### MISSILE IMPACT RATING: Large and Small Missile Impact Resistant.

**LABELING:** Each unit shall bear a permanent label with the manufacturer's name or logo, city, state, model/series, and following statement: "Miami-Dade County Product Control Approved", unless otherwise noted herein.

**RENEWAL** of this NOA shall be considered after a renewal application has been filed and there has been no change in the applicable building code negatively affecting the performance of this product.

**TERMINATION** of this NOA will occur after the expiration date or if there has been a revision or change in the materials, use, and/or manufacture of the product or process. Misuse of this NOA as an endorsement of any product, for sales, advertising or any other purposes shall automatically terminate this NOA. Failure to comply with any section of this NOA shall be cause for termination and removal of NOA.

**ADVERTISEMENT:** The NOA number preceded by the words Miami-Dade County, Florida, and followed by the expiration date may be displayed in advertising literature. If any portion of the NOA is displayed, then it shall be done in its entirety.

**INSPECTION:** A copy of this entire NOA shall be provided to the user by the manufacturer or its distributors and shall be available for inspection at the job site at the request of the Building Official.

This NOA revises and renews NOA# 13-0912.03 and consists of this page 1 and evidence pages E-1 and E-2, as well as approval document mentioned above.

The submitted documentation was reviewed by Manuel Perez, P.E.



*MP*  
9/26/14

NOA No. 14-0807.19  
Expiration Date: September 11, 2019  
Approval Date: October 09, 2014  
Page 1

Sunshine Windows Manufacturing, Inc.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

**A. DRAWINGS**

1. Manufacturer's die drawings and sections.  
*(Submitted under NOA# 03-0314.07)*
2. Drawing No PW01-14, titled "Series 4302 Aluminum Fixed Window - Impact Resistant Glass", sheets 1 through 8 of 8, dated 07/21/14, prepared by manufacturer, signed and sealed by Francisco Hernandez, P.E.

**B. TESTS**


1. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94  
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94  
3) Water Resistance Test, per FBC, TAS 202-94  
4) Large Missile Impact Test per FBC, TAS 201-94  
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94  
along with marked-up drawings and installation diagram of aluminum fixed window, prepared by Fenestration Testing Laboratory, Inc., Test Report No. FTL-7589, dated 02/18/14, signed and sealed by Marlin D. Brinson, P.E.
2. Test reports on: 1) Air Infiltration Test, per FBC, TAS 202-94  
2) Uniform Static Air Pressure Test, Loading per FBC TAS 202-94  
3) Water Resistance Test, per FBC, TAS 202-94  
4) Large Missile Impact Test per FBC, TAS 201-94  
5) Cyclic Wind Pressure Loading per FBC, TAS 203-94  
along with marked-up drawings and installation diagram of aluminum arch, eyebrow and rectangular fixed windows, prepared by Fenestration Testing Laboratory, Inc., Test Report No. FTL-3388, dated 08/14/02, signed and sealed by Joseph Chan, P.E.  
*(Submitted under NOA# 03-0314.07)*

**C. CALCULATIONS**

1. Anchor verification calculations and structural analysis, complying with FBC 5<sup>th</sup> Edition (2014) dated July 21, 2014, prepared, signed and sealed by Francisco Hernandez, P.E.
2. Glazing complies with ASTM E1300-09.

**D. QUALITY ASSURANCE**

1. Miami-Dade Department of Regulatory and Economic Resources (RER)



Manuel Perez, P.E.  
Product Control Examiner  
NOA No. 14-0807.19

Expiration Date: September 11, 2019  
Approval Date: October 09, 2014

Sunshine Windows Manufacturing, Inc.

NOTICE OF ACCEPTANCE: EVIDENCE SUBMITTED

**E. MATERIAL CERTIFICATIONS**


1. Notice of Acceptance No. **13-0129.27** issued to **E.I. DuPont DeNemours & Co., Inc.** for their "**DuPont Butacite® PVB Interlayer**" dated 04/11/13, expiring on 12/11/16.

**F. STATEMENTS**












1. Statement letter of conformance, complying with **FBC-5<sup>th</sup> Edition (2014)**, dated July 29, 2014, prepared, signed and sealed by Francisco Hernandez, P.E.
2. Statement letter of no financial interest, dated July 29, 2014, prepared, signed and sealed by Francisco Hernandez, P.E.
3. Laboratory compliance letter for Test Report No. **FTL-3388**, issued by Fenestration Testing Laboratory, Inc., dated 09/05/02, signed and sealed by Joseph Chan, P.E.  
(Submitted under NOA# 03-0314.07)

**G. OTHERS**

1. Notice of Acceptance No. **13-0912.03**, issued to Sunshine Windows Manufacturing, Inc. for their Series "4302" Aluminum Fixed Window – L.M.I., approved on 10/31/13 and expiring on 09/11/14.

  
Manuel Perez, P.E.  
Product Control Examiner  
NOA No. 14-0807.19  
Expiration Date: September 11, 2019  
Approval Date: October 09, 2014

FIXED WINDOW SHAPES  
INCLUDED IN THIS PRODUCT APPROVAL

			
RECTANGLE	RECTANGLE WITH CIRCLE TOP	RECTANGLE WITH ROUND TOP	ARCH
SEE SHEET 2 OF 8	SEE SHEET 2 OF 8	SEE SHEET 2 OF 8	SEE SHEET 3 OF 8
			
ELLIPSE	RECTANGLE WITH TRIANGLE TOP	ISOSCELES TRIANGLE WITH CURVED OR STRAIGHT SIDES	RIGHT TRIANGLE WITH CURVED OR STRAIGHT SIDES
SEE SHEET 3 OF 8	SEE SHEET 4 OF 8	SEE SHEET 5 OF 8	SEE SHEET 5 OF 8
			
FULL ROUND	HEXAGON	OCTAGON	
SEE SHEET 6 OF 8	SEE SHEET 6 OF 8	SEE SHEET 6 OF 8	

GENERAL NOTES:

- 1.- THIS PRODUCT MEETS THE REQUIREMENTS OF FBC 5TH EDITION (2014).
- 2.- SHUTTERS ARE NOT REQUIRED.
- 3.- REFERENCE TEST REPORT FTL-13-4904 DATED ON 3/13/2014.
- 4.- FOR ANCHOR TYPE AND SPACING REFER TO TYPICAL ELEVATIONS AND SECTIONS ON SHEET 2 THRU 7
- 5.- WOOD BUCKS (BY OTHERS) SHALL BE PROPERLY ATTACHED TO SUSTAIN AND TRANSFER LOADS IMPOSED BY GLAZING SYSTEM TO THE STRUCTURE AND SHALL BE APPROVED BY BUILDING OFFICIAL PRIOR TO WINDOW INSTALLATION.
- 6.- WOOD HOST STRUCTURE SHALL BE SOUTHERN YELLOW PINE G = 0.55 OF GREATER DENSITY.
- 7.- CONCRETE / MASONRY STRUCTURE FOR UNIT ATTACHMENT SHALL COMPLY WITH THE FOLLOWING REQUIREMENTS:
  - CONCRETE STRENGTH  $F_c'28 = 3000$  PSI MIN.
  - CMU AS PER ASTM C90. CMU MUST BE 8-INCH THICK, NORMAL WEIGHT BLOCKS WITH A MINIMUM COMPRESSIVE STRENGTH OF 1.9 KSI.
  - FILLED CMU  $F_m' = 2000$  PSI MIN.
- 8.- THE THICKNESS OF THE ALUMINUM HOST STRUCTURE SHALL BE NO LESS THAN 1/8". ALUMINUM SHALL BE 6063-T6.
- 9.- ALUMINUM IN CONTACT WITH DISSIMILAR MATERIALS SHALL BE PROTECTED (BY OTHERS) AS SPECIFIED IN FBC 5TH EDITION (2014).
- 10.- STEEL HOST STRUCTURE SHALL BE NO LESS THAN 18 GAUGE. STEEL SHALL BE  $F_y = 36$  KSI MIN.
- 11.- COLONIAL MUNTINS CAN BE APPLIED.
- 12.- USE NON-SHRINK, NON-METALIC HYDRAULIC CEMENT GROUT PER ASTM C1107/C1107M STANDARD SPECIFICATION FOR PACKAGED DRY.
- 13.- GLASS: 5/16" NOMINAL LAMINATED GLASS COMPOSED OF (2) 1/8" HEAT STRENGTHENED GLASS WITH 0.09" DUPONT BUTACITE PVB INTERLAYING FILM.
- 14.- FOR CORNER WELDED CONNECTIONS USE 1/8" FILLET WELD WITH 1/4" MINIMUM LENGTH MADE WITH ER4043 FILLER ALLOY.

PRODUCT REVISED  
as complying with the Florida  
Building Code  
Acceptance No 14-080719  
Expiration Date Sept. 11, 2019  
By *Manuel Perez*  
Miami Dade Product Control


*Francisco Hernandez*  
7/21/14  
FRANCISCO HERNANDEZ  
FLORIDA PE # 51393

Sunshine Windows  
Manufacturing, Inc.  
1745 W. 33rd Place  
Hialeah, Florida 33012  
Ph: (305)364-9952  
Fax: (305)828-5118


SERIES 4302 ALUMINUM  
FIXED WINDOW  
IMPACT RESISTANT GLASS

No DATE REVISION


DRAWING No.  
PW01-14  
DATE: 07/21/14  
SCALE: N.T.S.  
SHEET 1 OF 8



RECTANGLE  
TYPICAL ELEVATION






RECTANGLE WITH CIRCLE TOP  
TYPICAL ELEVATION



RECTANGLE WITH ROUND TOP  
TYPICAL ELEVATION

WINDOW SIZE W X H INCHES	DESIGN PRESSURES CHART - PSF	
	POS.	NEG.
108 X 26	80.00	80.00
91 X 26	80.00	80.00
84 X 26	80.00	80.00
78 X 37	80.00	80.00
78 X 26	80.00	80.00
78 X 19	80.00	80.00
74 X 39	80.00	80.00
74 X 37	80.00	80.00
74 X 26	80.00	80.00
74 X 19	80.00	80.00
63 X 46	67.83	67.83
63 X 39	80.00	80.00
63 X 37	80.00	80.00
63 X 26	80.00	80.00
63 X 19	80.00	80.00

WINDOW SIZE W X H INCHES	DESIGN PRESSURES CHART - PSF	
	POS.	NEG.
53 X 46	67.83	67.83
53 X 39	80.00	80.00
53 X 37	80.00	80.00
53 X 26	80.00	80.00
53 X 19	80.00	80.00
46 X 46	67.83	67.83
46 X 39	80.00	80.00
46 X 37	80.00	80.00
46 X 26	80.00	80.00
46 X 19	80.00	80.00
38 X 37	80.00	80.00
38 X 26	80.00	80.00
38 X 19	80.00	80.00
26 X 26	80.00	80.00
26 X 19	80.00	80.00



GENERAL NOTES:  
1.- FOR GENERAL NOTES REFER TO SHEET 1 OF 8.

PRODUCT REVISED  
as complying with the Florida  
Building Code  
Acceptance No. 14-0807.19  
Expiration Date 5/11/2019  
By *Manuel J. Hernandez*  
Miami Dade Product Control


*Francisco Hernandez*  
7/21/14  
FRANCISCO HERNANDEZ  
FLORIDA PE # 51393

Sunshine Windows  
Manufacturing, Inc.  
1745 W. 33rd Place  
Hialeah, Florida 33012  
Ph: (305)364-9952  
Fax: (305)828-5118

SERIES 4302 ALUMINUM  
FIXED WINDOW  
IMPACT RESISTANT GLASS

DATE	REVISION

DRAWING No.  
PW01-14  
DATE: 07/21/14  
SCALE: N.T.S.  
SHEET 2 OF 8




**ARCH  
TYPICAL ELEVATION**

WINDOW SIZE W X H INCHES	DESIGN PRESSURES CHART - PSF ( ARCH )	
	POS.	NEG.
108 X 26	80.00	80.00
91 X 26	80.00	80.00
84 X 26	80.00	80.00
78 X 37	80.00	80.00
78 X 26	80.00	80.00
78 X 19	80.00	80.00
74 X 37	80.00	80.00
74 X 26	80.00	80.00
74 X 19	80.00	80.00
63 X 26	80.00	80.00
63 X 19	80.00	80.00
53 X 26	80.00	80.00
53 X 19	80.00	80.00
46 X 19	80.00	80.00
38 X 19	80.00	80.00


WINDOW SIZE W X H INCHES	DESIGN PRESSURES CHART - PSF ( ELLIPSE )	
	POS.	NEG.
78 X 37	80.00	80.00
78 X 26	80.00	80.00
78 X 19	80.00	80.00
74 X 39	80.00	80.00
74 X 37	80.00	80.00
74 X 26	80.00	80.00
74 X 19	80.00	80.00
63 X 46	67.83	67.83
63 X 39	80.00	80.00
63 X 37	80.00	80.00
63 X 26	80.00	80.00
63 X 19	80.00	80.00
53 X 46	67.83	67.83
53 X 39	80.00	80.00
53 X 37	80.00	80.00
53 X 26	80.00	80.00
53 X 19	80.00	80.00
46 X 46	67.83	67.83
46 X 39	80.00	80.00
46 X 37	80.00	80.00
46 X 26	80.00	80.00
46 X 19	80.00	80.00
38 X 37	80.00	80.00
38 X 26	80.00	80.00
38 X 19	80.00	80.00
26 X 26	80.00	80.00
26 X 19	80.00	80.00

**GENERAL NOTES:**

1.- FOR GENERAL NOTES REFER TO SHEET 1 OF 8.



**ELLIPSE  
TYPICAL ELEVATION**



PRODUCT REVISED  
as complying with the Florida  
Building Code  
Acceptance No. 14-080219  
Expiration Date Sept. 11, 2019  
By *Manuel Perez*  
Miami Dade Product Control

*Folt*  
7/21/14  
FRANCISCO HERNANDEZ  
FLORIDA PE # 51393


**Sunshine Windows  
Manufacturing, Inc.**  
1745 W. 33rd Place  
Hialeah, Florida 33012  
Ph: (305)364-9952  
Fax:(305)828-5118

**SERIES 4302 ALUMINUM  
FIXED WINDOW  
IMPACT RESISTANT GLASS**

No	DATE	REVISION

DRAWING No.  
**PW01-14**  
DATE: 07/21/14  
SCALE: N.T.S.

SHEET 3 OF 8




Sunshine Windows  
Manufacturing, Inc.  
1745 W. 33rd Place  
Hialeah, Florida 33012  
Ph: (305)364-9952  
Fax:(305)828-5118

SERIES 4302 ALUMINUM  
FIXED WINDOW  
IMPACT RESISTANT GLASS


No	DATE	REVISION

DRAWING No.  
PW01-14  
DATE: 07/21/14  
SCALE: N.T.S.  
SHEET 4 OF 8


WINDOW SIZE H X W INCHES	DESIGN PRESSURES CHART - PSF	
	POS.	NEG.
26 X 108	80.00	80.00
26 X 91	80.00	80.00
26 X 84	80.00	80.00
37 X 78	80.00	80.00
26 X 78	80.00	80.00
19 X 78	80.00	80.00
39 X 74	80.00	80.00
37 X 74	80.00	80.00
26 X 74	80.00	80.00
19 X 74	80.00	80.00
46 X 63	67.83	67.83
39 X 63	80.00	80.00
37 X 63	80.00	80.00
26 X 63	80.00	80.00
19 X 63	80.00	80.00
46 X 53	67.83	67.83
39 X 53	80.00	80.00
37 X 53	80.00	80.00
26 X 53	80.00	80.00
19 X 53	80.00	80.00
46 X 46	67.83	67.83
39 X 46	80.00	80.00
37 X 46	80.00	80.00
26 X 46	80.00	80.00
19 X 46	80.00	80.00
37 X 38	80.00	80.00
26 X 38	80.00	80.00
19 X 38	80.00	80.00
26 X 26	80.00	80.00
19 X 26	80.00	80.00




RECTANGLE WITH TRIANGLE TOP  
TYPICAL ELEVATION



CORNER DETAIL # 1



CORNER DETAIL # 2




CORNER DETAIL # 3

GENERAL NOTES:  
1.- FOR GENERAL NOTES REFER TO SHEET 1 OF 8.


PRODUCT REVISED  
as complying with the Florida  
Building Code  
Acceptance No 14-080719  
Expiration Date Sept 11, 2019  
By *Manuel Jaz*  
Miami Dade Product Control

*Francisco Hernandez*  
7/21/14  
FRANCISCO HERNANDEZ  
FLORIDA PE # 51393




WINDOW SIZE H X W INCHES	DESIGN PRESSURES CHART - PSF	
	POS.	NEG.
63 X 46	67.83	67.83
63 X 39	80.00	80.00
63 X 37	80.00	80.00
53 X 46	67.83	67.83
53 X 39	80.00	80.00
53 X 37	80.00	80.00
53 X 26	80.00	80.00
46 X 46	67.83	67.83
46 X 39	80.00	80.00
46 X 37	80.00	80.00
46 X 26	80.00	80.00
38 X 37	80.00	80.00
38 X 26	80.00	80.00
38 X 19	80.00	80.00
26 X 26	80.00	80.00
26 X 19	80.00	80.00



ISOSCELES TRIANGLE WITH CURVED OR STRAIGHT SIDES  
TYPICAL ELEVATION



RIGHT TRIANGLE WITH CURVED OR STRAIGHT SIDES  
TYPICAL ELEVATION



GENERAL NOTES:

1.- FOR GENERAL NOTES REFER TO SHEET 1 OF 8.

PRODUCT REVISED  
as complying with the Florida  
Building Code  
Acceptance No. 14-0007-19  
Expiration Date Sept 11, 2019  
By Francisco Hernandez  
Miami Dade Product Control

7/21/14  
FRANCISCO HERNANDEZ  
FLORIDA PE # 51393




Sunshine Windows  
Manufacturing, Inc.  
1745 W. 33rd Place  
Hialeah, Florida 33012  
Ph: (305)364-9952  
Fax: (305)828-5118

SERIES 4302 ALUMINUM  
FIXED WINDOW  
IMPACT RESISTANT GLASS



No	DATE	REVISION

DRAWING No.  
PW01-14  
DATE: 07/21/14  
SCALE: N.T.S.  
SHEET 5 OF 8





WINDOW SIZE WIDTH INCHES	DESIGN PRESSURES CHART - PSF	
	POS.	NEG.
53	58.87	58.87
48	65.00	65.00
46	67.83	67.83
43	72.56	72.56
W ≤ 39	80.00	80.00



GENERAL NOTES:

1.- FOR GENERAL NOTES REFER TO SHEET 1 OF 8.

PRODUCT REVISED  
as complying with the Florida  
Building Code  
Acceptance No. 14-0807.19  
Expiration Date Sept. 11, 2019  
By *Manuel Hernandez*  
Miami Dade Product Control


*Francisco Hernandez*  
7/21/14  
FRANCISCO HERNANDEZ  
FLORIDA PE # 51393

Sunshine Windows  
Manufacturing, Inc.  
1745 W. 33rd Place  
Hialeah, Florida 33012  
Ph: (305)364-9952  
Fax: (305)828-5118


SERIES 4302 ALUMINUM  
 FIXED WINDOW  
 IMPACT RESISTANT GLASS

NO	DATE	REVISION


DRAWING No.  
PW01-14  
DATE: 07/21/14  
SCALE: N.T.S.  
SHEET 6 OF 8




ATTACHMENT TO CONCRETE  
THROUGH 1 X WOOD BUCK




ATTACHMENT TO PRE-CAST SILL



ATTACHMENT TO WOOD



ATTACHMENT TO MULLION



ATTACHMENT TO METAL STRUCTURE

## TYPICAL HEAD, SILL AND JAMB SECTIONS

PRODUCT REVISED  
as complying with the Florida  
Building Code  
Acceptance No. 14-0807-19  
Expiration Date Sept. 11, 2019  
By *Manuel Perez*  
Miami-Dade Product Control

7/21/14  
FRANCISCO HERNANDEZ  
FLORIDA PE # 51393

Sunshine Windows  
Manufacturing, Inc.

1745 W. 33rd Place  
Hialeah, Florida 33012  
Ph: (305)364-9952  
Fax: (305)828-5118

SERIES 4302 ALUMINUM  
FIXED WINDOW  
IMPACT RESISTANT GLASS


No	DATE	REVISION

DRAWING No.  
PW01-14


DATE: 07/21/14

SCALE: N.T.S.

SHEET 7 OF 8




SECTION A-A




SECTION B-B


MATERIAL LIST			
ITEM #	PART	DESCRIPTION	MATERIAL
1	43681	HEAD, SILL AND JAMB	6063-T6
2	30684	GLAZING BEAD	6063-T6
3	GLAZING BEAD BULB	WEATHER STRIPING	FPVC DUR: 75 +/- 5
4	# 8" X 1" PH S.D.S.	ASSEMBLY SCREW	STEEL
5	5/16" LAMINATED GLASS/HEAT STR.	SEE GLAZING DETAIL THIS SHEET	GLASS
6	DOW CORNING 899	SEALANT	SILICONE



GLAZING DETAIL




1



2

PRODUCT REVISED  
as complying with the Florida  
Building Code  
Acceptance No. 14-0307-19  
Expiration Date Sept. 11, 2019  
By *Francisco Hernandez*  
Miami Dade Product Control

*Francisco Hernandez*  
7/21/14  
FRANCISCO HERNANDEZ  
FLORIDA PE # 51393



Sunshine Windows  
Manufacturing, Inc.  
1745 W. 33rd Place  
Hialeah, Florida 33012  
Ph: (305)364-9952  
Fax: (305)828-5118

SERIES 4302 ALUMINUM  
FIXED WINDOW  
IMPACT RESISTANT GLASS

No	DATE	REVISION

DRAWING No.  
PW01-14  
DATE: 07/21/14  
SCALE: N.T.S.  
SHEET 8 OF 8